KOLAR DIVISION.

Notice, dated 31st March 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 25th April 1899 (inclusive) for restoring Yeragudi Tank Reg. No. 106 Bagepalli taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1900.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for restoring Yerragudi Tank Reg. 106, Bagepalli taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Eastern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantity of work required for restoring Yerragudi Tank Reg. No. 106, Bagepalli taluk :-

Bund— *Items of work.*	*Per.*	*Quantity.*
Turfing	S. yds.	4,944
Earthwork	C. yds.	5,808
Breach filling	"	2,655
Grade stones with bottom and index stones including numbering	No.	22
Bell stones	"	2
Tank No. stones	"	1
Gauge stones	"	1
Clearing jungle and cutting trees	L. S.	Rs. 50
Benching rock, &c	"	50
Core wall, brick in surki mortar	C. ft.	675
Old stone work	C. yd.	1,463
New stone work	"	1,455
Sluice No. 2—		
Cutting and refilling	C. yd.	756
Earthwork excavation	"	23
Burnt brick in surki mortar	C. ft.	1,081
Burnt stone slabs	S. ft.	539
Plastering with mortar	Sqr.	8·00
Cutting orifice stone with plug, &c.	L. S.	Rs. 10
No. 1 Sluice—		
Cutting and refilling	C. yd.	756
Earthwork excavation	"	23
Burnt brick in surki mortar	C. ft.	1,081
Burnt stone slabs	S. ft.	539
Plastering with mortar	Sqr.	8·00
Cutting orifice stone with plug, &c.	L. S.	Rs. 10
Sluice No. 3—		
Constructing a tunnel in codi right	L. S.	50
Left codi 50 feeet long—		
Benching rock	S. ft.	168
Burnt brick in surki mortar	C. ft.	261
Burnt stone slabs	S. ft.	132
Plastering with mortar	Sqr.	3·60
Burnt stone in chunam, including pointing	C. ft.	492
Rough stone work	C. yd.	33
Date stone cutting in coping slab	L. S.	Rs. 3
Right codi 140 feet long—		
Earthwork excavation	C. yd.	136
Burnt brick in surki mortar	C. ft	2,270
Burnt stone in chunam	C. ft.	848
Plastering with mortar	Sqr.	11·64
Pointing with chunam	"	2·79
Burnt stone slabs	S. ft.	720
Rough stone sajicut	C. yd.	63
Repairing the old apron	L. S.	Rs. 25
Rough stone work	C. yd.	30

V. ARUNACHALA MUDALIAR, *Offg. Exec. Engr.*